



Certificate of Compliance

This certificate is issued for the following:

Sprinkler System Alarm Test Devices

Test and Drain Valves

<i>Model Designation</i>	<i>Size, inch NPS</i>	<i>Nominal K-Factor</i>	<i>Rated Working Pressure, psi (kPa)</i>	<i>Remarks</i>
VTN01-025	1	2.8, 4.2, 5.6, 8.0	300 (2070)	a
VTN01-032	1-1/4	2.8, 4.2, 5.6, 8.0	300 (2070)	a
VTN01-040	1-1/2	2.8, 4.2, 5.6, 8.0	300 (2070)	a
VTN01-050	2	2.8, 4.2, 5.6, 8.0	300 (2070)	a

Remarks:

- a. Devices supplied with female NPT or female BSPT end connections.

Prepared for:

FlowCom Mechanical Technology Co Ltd
Unit 2-801, No. 2388 Xiupu Rd
Pudong, Shanghai 201315
China

FM Approvals Class: 1625 (December 2009)

Approval Identification: PR453251

Approval Granted: September 15, 2020

To verify the product continues to be Approved please refer to www.approvalguide.com.

Said Approval is subject to satisfactory field performance, continuing Surveillance Audits, and strict conformity to the constructions as shown in the Approval Guide, an online resource of FM Approvals.

David B. Fuller

VP, Manager – Fire Protection

FM Approvals

1151 Boston-Providence Turnpike

Norwood, MA 02062

